

**BIDS AND AWARDS COMMITTEE**  
**Supplemental Bid Bulletin No. 1**

This Supplemental Bid Bulletin dated December 7, 2022, is issued to change some conditions and/or requirements posted in the Bidding Documents. This shall form an integral part of the Bidding Documents of the project entitled **CONSTRUCTION OF HFG MULTI-PURPOSE BUILDING (ADVANCE PROCUREMENT)** with PhilGEPS Reference No. **9225891**.

A. Please be advised of the following changes on the **Bidding Documents** to wit;

**Section VIII. Bill of Quantities**

Stock #	Unit	Item Description	Quantity
1	LUMP SUM	Clearing and Grubbing	1.00
2	CU.M.	Excavation of footing	213.79
3	CU.M.	Embankment	134.00
4	CU.M.	Backfilling of Excavated Materials	159.53
5	CU.M.	Structural Concrete Structural Concrete (Class "A") 21 Mpa	77.27
6	KG/S	Reinforcing Steel	10643.00
7	LUMP SUM	Forms and Falseworks	1.00
8	Lin.M.	Sewerage System	57.00
9	UNIT/S	Catch Basins	4.00
10	Lin.M.	Storm Drainage and Downspouts	42.00
11	PC/S	Plumbing Works (includes water closet and wall hung lavatory with complete accessories, bidet and faucet)	48.00
12	SQ.M	Ceiling (fiber cement board)	141.14
13	SQ.M	Ceiling Works (UPvc ceiling boards @ stage area)	23.70
14	SQ.M	Ceiling (pre-painted metal panel)	63.90
15	LUMP SUM	Aluminum Glass Window	1.00
16	set/s	Panel Door Metal with bottom louver on metal jambs and lever type stainless lockset	2.00
17	set/s	Pre-painted Metal Roofing with 10mm double sided aluminum foam insulation	209.50
18	SQ.M	Waterproofing (cementitious waterproofing slurry and fast setting hydraulic cement) roof slab	45.21
19	SQ.M	GLAZED TILES for toilets	18.22
20	SQ.M	UNGLAZED Tile (for toilets)	4.29
21	SQ.M	GRANITE Tile	148.27
22	SQ.M	Cement Plaster Finish	506.02
23	SQ.M	Masonry Painting	506.02
24	SQ.M	Ceiling Painting	141.14
25	LUMP SUM	Other Supplies Aluminum Ventilation Louvers on Aluminum Frame w/ Screen	1.00
26	SQ.M	Masonry Works (100mmCHB)	75.71
27	SQ.M	Masonry Works (6"CHB) (ZF-1 and Septic Tank)	177.30
28	KG/S	Structural Steel Roof Framing	2374.71
29	Lin.M.	Conduit, Boxes and Fittings	603.00
30	Lin.M.	Wires and Wiring Devices (Switches with Light indicator and Convenience outlet with Ground)	1680.00
31	SET	Panel Board (16 Branches), Main Breaker - 100/A, CKT Breaker (15A-6 pcs, 20A-4pcs, 30A-6pcs)	18.00
32	SET	Lighting Fixtures (53sets) and Industrial Wall Fans 18" (8sets)	162.00
33	LUMP SUM	Personal Protective Equipment (PPE) Occupational	1.00
34	LUMP SUM	TEMPORARY FACILITIES Temporary storage (insie) and temporary barracks rental (outside the compound)	1.00

Other specifications and conditions of the contract not reflected in this Supplemental/Bid Bulletin but indicated in the Bidding Documents shall remain the same and shall form part of the requirements.

For the guidance and information of all concerned.

**JEAN PAUL S. PARAJES**

Chairperson  
Bids and Awards Committee